(15)

BRUHATH BANGALORE MAHANAGARA PALIKE, DASARAHALLI ZONE
Office of the Executive Engineer

DTS COPY

NAME OF WORK: Ward Maintanance for Gangmens, Tractors & JCB for Removing silt & debries in the drains road side burms in Dasarahalli ward No 14

Sl. No	Description of work	Unit	Qty	Rate to be Quoted	
				In Figures (Rs.)	In Words (Rs.)
1	2	3	4	5	6
1	Removing B.S. slab of drain and stacking with all leads and lifts etc., Complete as per specification and direction of Engineer-in-charge of the work.	Sqm	1777.50		
2	Excavation and removal of silt and silt mix with sand in slushy condition form canal bed including disposing of the same in spoil bank or on canal embankment in layers as directed etc., Complete as per specification and direction of Engineer-in-charge of the work.	Cum	2049.30		
3	Refixing stone slabs of drains and pointing in CM 1:3 with all leads and lifts etc., Complete as per the direction of Engineer-in-charge of the work.	Sqm	1777.50		
4	J.C.B. Excavator on hire basis including JCB Operator with Helper to carryout the works on emergency Complete as per the direction of Engineer-in-charge of the work.	Days	35.00		
5	Tractor 40 HP on hire basis including Tractor Driver with Helper to carryout the works on emergency Complete as per the direction of Engineer-in-charge of the work.	Days	120.00		

Number of Corrections: 02

Signature of the Contractor

Executive Engineer,
Dasarahalli Division,

DTS Approved

Chief Engineer
Bruhath Bangalore Mahanagara Palike
Dasarahalli Zone, Bangalore.